

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of the Work : Construction of Bus Stop in Ramachandrapura in Ward No. 10, Daddabommasandra, Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	42.83	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. etc complete as per specifications and directions of engineer in charge of the work	Cum	Rs.198.22	
2	8.94	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, coarse aggregates @ 0.85 cum and fine aggregates @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	Rs.3,812.82	
3	11.66	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	Rs.198.22	
4	8.49	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal , coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplasticiser @ 3lts conforming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc complete as per specifications and directions of engineer in charge of the work	Cum	Rs.5,142.06	

Quantity.	Description	Unit	Rates	
			In Figures	In Words
5	19.01	Providing Mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work	Rs.7,690.30	
		Qtl		
6	2.81	Supplying, fabricating, erecting, and fixing in position, inserts and embedments, Truss, clamps, brackets, insert plates and all miscellaneous steel works as shown in drawing and as directed by the Engineer at all depths, using MS angles, channels, steel beams, rails, tees, plates, flats, rounds squares etc., of various sizes and other structural section confirming IS 2062 grade A, medium class GI pipes etc., including straighting, cutting, fabricating, welding, bending to slope fixing to position, welding to insert plate embeded in concrete and inclusive of 2coats of enamel paint over one coat of metal primer. The rate quoted is to include the cost of all materials, labour, tools, tackets, cranes, devices and plants, wastage etc., as per specifications and drawings complete. Including cost of bolts, nuts, washers, clamps, welding, electrodes, and connections required for the work. Rate to include shims and packing peices etc., complete with all lead and lifts as directed by the Engineer-in-charge.	Rs.85,000.00	
		MT		
7	48.12	Manufacturing, providing & fixing Advertisement Boards with frame of 25x25x2mm sq.pipe and S.S Beading with rivets with 1.2mm thick polycarbonate sheet covering as per approved drawing & specification etc., complete and as directed by the Engineer in charge	Rs.3,000.00	
		Sqm		
8	9.60	Providing and fixing stainless steel hand rails for a height of 900 mm using m 62.50 mm dia of 16 guage for top measure and verticals at 1.50 m C/c, and 50 mm dia of 16 guage stainless steel pipes of 4 rows below top measure at equal intervals including fixing with 500 mm dia, G.L pipe including cutting, welding, be4nding wherever necessary with suitable caps at top and bottom etc, complete finishing with mat / shnining finishing etc, complete as per technical specification and as directed by the engineer in charge or work, etc complete as per specifications and directions of engineer in charge of the work	Rs.4,282.40	
		M		
9	38.71	Galvalume Steel Sheet Roofing: Providing galvolume sheet roofing fixed with polymer etc complete as per specifications and directions of engineer in charge of the work	Rs.1,137.00	
		Sqm		
10	38.71	Providing & fixing 84C Steel Flase Ceiling with panel of 0.5mm thick with necessary fitings etc complete and as per directions of Engineer-In-Charge.	Rs.1,500.00	
		Sqm		
11	4.29	Providing & fixing Granite Seating with necessary fitings etc complete and as per directions of Engineer-In-Charge.	Rs.3,500.00	
		Sqm		

Quantity.	Description	Unit	Rates	
			In Figures	In Words
12	6.01	Providing and laying in position plain cement concrete of mix M15 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	Rs.4,327.98
13	37.92	Providing and laying flooring using pre polishing water cut/gang saw 19 mm thick Granite slab over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement / colour pigment etc complete as per specifications and directions of engineer in charge of the work	Sqm	Rs.1,708.72

R. Narayana

Signature of the Contractor

[Signature]

Executive Engineer

Byatarayanapura Division

BBMP, Bangalore - 92

ಕರಡು ಟೆಂಡರ್ ಪಡ್ಯಲ್ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ 18/11/2013
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

[Signature]

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ಪಲಯ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92

18/11/2013